



DANCOVER[®]



Manual
for
Greenhouse
TITAN Arch 196





DESCRIPTION

The "TITAN Arch 196" greenhouse is designed and manufactured in accordance with SNiP 2.10.04-85 and generally intended for industrial cultivation of crops at farms and peasant holdings.

Width of the greenhouse is 7.46 m. Area of covered ground depends on the length of the greenhouse and for minimal length of 4.2 m is 31.5 m². Height of the installed frame is 3.8 m. Required length of the greenhouse is provided by purchasing of extra packages «Insert» and adds 2.1 m to the base length (table 1). The frame of the greenhouse is made of galvanized iron 1 mm thick and is to be assembled with screws, nuts and washers.

The greenhouse is fixed on the ground without foundation by digging special frame endings or on a fundament using cleater angles. The type of fixing is determined by a buyer. The kit includes everything you need to mount the covering. The greenhouse may be completed with covering on buyer's request. Number of gates, doors, small windows is conformed to a buyer and the complete set of an anteroom is conformed to a buyer.

L greenhouse length, m	N - number of greenhouse sections, excluding	FRAME (basic length 4,2 m)										INSERT (frame extension for 2,1 m)						
		1 TITAN Arch 196 Package	2 TITAN Arch 196 Package	3 TITAN Arch 196 Package	4 TITAN Arch 196 Package	5 TITAN Arch 196 Package	6 TITAN Arch 196 Package	7 TITAN Arch 196 Package	8 TITAN Arch 196 Package	9 TITAN Arch 196 Package	10 TITAN Arch 196 Package	EXTRA PACKAGE	1 INSERT PACKAGE	2 INSERT PACKAGE	3 INSERT PACKAGE	4 INSERT PACKAGE	EXTRA PACKAGE	
4,2	0																	
6,3	1											1	1	1	1	1		
8,5	2											2	2	2	2	2		
10,6	3											3	3	3	3	3		
12,7	4											4	4	4	4	4		
14,9	5	1	1	2	2	2	2	2	2	2	1	5	5	5	5	5		
17,0	6											6	6	6	6	6		
19,1	7											7	7	7	7	7		
21,2	8											8	8	8	8	8		
23,4	9											9	9	9	9	9		
2,1(N+2)												N	N	N	N	N		

Package name	quantity	dimensions (mm)	max. allowable
Tambour	1	2700x100x100	31
Door	1	1900x100x50	14,2
Tambour packaging	1	200x100x50	1,3
Door sealing	1	500x300x50	1,2
Side wall sealing	1	500x300x50	3,1

*Completing with one anteroom or more is made at the request of the buyer (purchased separately).

content	dimensions,mm	weight,no More,kg
FRAME (BASE LENGTH 4.2 M)		
1 PACKAGE TITAN Arch 196 (arc elements)	3100x200x100	15,0
2 PACKAGE TITAN Arch 196 (power arc straight elements)	2800x100x90	28,0
3 PACKAGE TITAN Arch 196 (end runners elements)	2000x90x100	41,0
4 PACKAGE TITAN Arch 196 (end side brace elements)	2400x90x100	23,0
5 PACKAGE TITAN Arch 196 (arc elements)	3100x200x100	15,0
6 PACKAGE TITAN Arch 196 (end straight elements and strips)	2800x200x100	41,0
7 PACKAGE TITAN Arch 196 (end straight elements)	2800x200x100	34,0
8 PACKAGE TITAN Arch 196 (elements and strips for doors)	500x300x100	14,0
9 PACKAGE TITAN Arch 196 (elements and strips for gates)	2700x100x90	37,0
10 PACKAGE TITAN Arch 196 (fixtures, component parts and seal)	500x300x100	19,5
EXTRA PACKAGE		
INSERT (2.1 M FRAME ELONGATION)		
1 PACKAGE INSERT (arc elements)	3100x200x100	15,0
2 PACKAGE INSERT (power arc straight elements)	2800x100x90	32,0
3 PACKAGE INSERT (runners elements)	2100x110x90	43,0
4 PACKAGE INSERT (fixtures and component parts for Insert)	200x100x50	2,0
EXTRA PACKAGE		

Table 4 DETAILED PARTS LIST "FRAME" (4.2 m)			
marking	name	quantity(pcs)	length (m)
1 PACKAGE TITAN Arch 196			
4	Arc	4	3,08
2 PACKAGE TITAN Arch 196			
5н	Bottom arc strainer	2	2,73
5	Top arc strainer	2	2,73
6	Segment strainer	3	2,58
7м	Radial strainer 1	4	0,3
76	Radial strainer 2	3	0,54
3	Support	2	0,29
1	Foundation stay brace	2	0,84
3 PACKAGE TITAN Arch 196			
2к	End runner	13	1,99
2кн	Bottom end runner	4	1,99
4 PACKAGE TITAN Arch 196			
Укос	Longitudinal stiffness side brace	8	2,36
5 PACKAGE TITAN Arch 196			
4	Arc	4	3,08
6 PACKAGE TITAN Arch 196			
11	Top girder	2	2,7
15ц	Central vertical member	1	0,6
15	Side vertical member	2	0,55
9	Stay brace	4	2,7
10	Cross bar	5	1,07
8	Side brace	2	1,31
10ц	Central strainer	1	2,72
П-11	Strip of a top girder	1	2,67
П-9	Strip of a gate opening stay brace	2	2,62
П-10	Strip of a cross bar	1	1,01
П-12-д	Strip of a door opening stay brace	1	1,9
7 PACKAGE TITAN Arch 196			
5н	Bottom arc strainer	2	2,73
5	Arc strainer	2	2,73
6	Segment strainer	1	2,58
7м	Radial strainer 1	4	0,3
76	Radial strainer 2	1	0,54
1	Foundation stay brace	6	0,84
3	Support	6	0,29
П-5н	Strip of a bottom arc strainer	6	1,24
	Ridge side brace	1	2,23
	Strip of a ridge side brace	2	0,03
8 PACKAGE TITAN Arch 196			
13-д	Door cleat	2	0,95
13-д-н	Door bottom cleat	1	0,95
12-д-л	Door left stay brace	1	1,88
12-д-п	Door right stay brace	1	1,88
14-д	Door diagonal	2	1,23
П-12-д-п	Strip of a door right stay brace	1	1,88
П-13-д-н	Strip of a door bottom cleat	1	0,95
16к	Guiding bracket	4	0,08
	Hasp	2	0,65

Table 4 DETAILED PARTS LIST "FRAME" (4.2 m)			
marking	name	quantity(pcs)	length (m)
9 PACKAGE TITAN Arch 196			
13-в	Gates cleat	4	1,28
13-в-н	Gates bottom cleat	2	1,28
12-в-п	Gates right stay brace	2	2,61
12-в-л	Gates left stay brace	2	2,60
16-к	Guiding bracket	8	0,08
14-в	Hinged gate diagonal	4	1,73
П-12-в-п	Strip of a right stay brace	2	2,61
П-13-в-н	Strip of a bottom cleat	2	1,28
	Hasp	4	0,91
10 PACKAGE TITAN Arch 196			
	Screw M6x10 DIN 965	460	
	Bolt M6x14 DIN 933	1192	
	Bolt M6x20DIN 933	120	
	Nut M6 DIN 934	1772	
	Bracket 26x17x16 (angle)	352	
	Hanger	18	
	Hinge ПН 1-130 left	4	
	Hinge ПН 1-130 right	8	
	Straight lug 40x90	8	
	Pull PC-80-2	6	
	Self-driving screw M5x20	352	
	Washer 6	1344	
	Washer 32x6	450	
	Penofol	1	21,4
	Door seal	1	35,6
	End seal	1	24 м
EXTRA PACKAGE (BASE)			
	Ridge	2	2,10
	Top draw band	3	10,91
	Bottom draw band	6	0,60
Ф.ПП.Д	Arc base sheet	4	2,91
Ф.ПП.К	Outermost base sheet for a runner	4	1,95
	Tingle	24	0,09
Ф.ПК	Outermost shape	4	2,10
	Washer 32x6	24	
	Bolt M6x14	56	
	Bolt M6x20	24	
	Bolt M6x60	6	
	Nut M6	86	
	Washer 6	88	
	Double-size scotch tape	2	5 м

Table 5 DETAILED PARTS LIST "INSERT"			
marking	name	quantity(pcs)	length (m)
1 PACKAGE INSERT			
4	Arc	4	3,08
2 PACKAGE INSERT			
5н	Bottom arc strainer	2	2,73
5	Arc strainer	2	2,73
6	Segment strainer	3	2,58
7м	Radial strainer 1	4	0,3
7б	Radial strainer 2	3	0,54
П-5н	Strip of a bottom arc strainer	4	1,24
3	Support	2	0,29
1	Foundation stay brace	2	0,84
3 PACKAGE INSERT			
2	Main runner	13	2,08
2н	Main runner	4	2,08
4 PACKAGE INSERT			
	Screw M6x10 DIN 965	52	
	Bolt M6x14 DIN 933	164	
	Bolt M6x20DIN 933	40	
	Nut M6 DIN 934	256	
	Washer 6	304	
EXTRA PACKAGE INSERT			
	Ridge	1	2,10
	Top draw band	1	10,91
	Bottom draw band	2	0,60
Ф.П.Д	Arc base sheet	4	2,91
Ф.П.О	Outermost base sheet for a runner	2	2,04
	Tingle	24	0,09
Ф.П	Main shape	2	2,10
	Washer 32x6	12	
	Bolt M6x14	38	
	Bolt M6x20	12	
	Bolt M6x60	2	
	Nut M6	52	
	Washer 6	54	
	Double-size scotch tape	1	5 м

Table 6 DETAILED PARTS LIST "ANTEROOM"			
marking	name	quantity(pcs)	length (m)
1 PACKAGE ANTEROOM			
15	Side vertical member	1	0,55
9	Stay brace	2	2,7
10	Cross bar	2	1,07
8	Side brace	1	1,31
1	Foundation stay brace	2	0,84
3	Support	2	0,28
2кн	Bottom end runner	5	1,99
10ц-т	Central strainer	1	1,28
П-9	Strip of a gate opening stay brace	1	1,9
П-10	Strip of a cross bar	1	1,0
2 PACKAGE ANTEROOM			
13-д	Door cleat	2	0,95
13-д-н	Strip of a door bottom cleat	1	0,95
12-д-л	Door left stay brace	1	1,88
12-д-п	Door right stay brace	1	1,88
14-д	Door diagonal	2	1,23
П-12-д-п	Strip of a door right stay brace	1	1,88
П-13-д-п	Strip of a door bottom cleat	1	0,95
	Bracket	4	0,84
	Hasp	2	0,65
Anteroom seal			
	Door seal	1	6 м
	End seal	1	8 м
Anteroom prepacking			
	Screw M6x10	78	
	Bolt M6x14	123	
	Bolt M6x20	50	
	Nut M6	251	
	Bracket 26x17x16	97	
	Hanger	3	
	Hinge ПН 1-130 left	2	
	Straight lug 40x90	2	
	Pull PC-80-2	2	
	Self-driving screw	97	
	Washer 6	91	

WARRANTY LIABILITIES

1. The manufacturer bears responsibility for the greenhouse frame complete setup.
2. The manufacturer bears responsibility for the greenhouse assemblability in accordance with the manual.
3. The manufacturer bears responsibility for the greenhouse durability under specified magnitude of atmospheric actions.
4. Claim presentation period is 12 months from the date of purchase.

WARRANTY CONDITIONS

Warranty liabilities do not apply to cases of:

1. Greenhouse installation with violation of requirements of the manual.
2. Violation of the rules of operation.
3. Inappropriate use of the greenhouse.
4. Floods, hurricanes and other natural disasters.

The manufacturer reserves the right for greenhouse engineering design changes.

RULES OF OPERATION



It is not allowed to install the greenhouse without fastening on the ground because of the large sail area of the greenhouse and the possibility of floating away the unfastened greenhouse.

The greenhouse should be serviced in the winter period. The greenhouse has durability under the action of snow loads way more than is required for greenhouses, but less for some snow areas in comparison with the general construction standards. According to SNIP 2.10.04-85 «Greenhouses and seedbeds» «weight of snow blanket on 1 m² of horizontal surface of the ground in design of static greenhouses...» should be taken from 10 to 40 kg/m² depending on a snow region. This is much less than the general construction standards for snow load, because it is assumed that on the current greenhouses a snowcap is not preserved until the next snowfall. According to the results of strength tests the limits of durability of the greenhouse frame are revealed: destroying snow load is 196 kg/m², permissible load (with safety coefficient 1.4) – 140 kg/m².

The permissible load approximately corresponds to the thickness of fresh snow 0.9 m and settled snow 0.45 m. Thus, in operation it is necessary to prevent accumulation of snowcaps above specified limits.

If the greenhouse is not heated in winter, or it is supposed to use the greenhouse as an unheated housing, awning, warehouse, etc., it is necessary to control the snowcap (to shift the snow down with a wooden or plastic scraper, installed on a pole). For these variants of operation it is possible to supply reinforced frames with a reduced interval between the power arcs under the snow load specified by the customer.

Do not allow damage to the frame, and if it happened, then hold timely repairs

OPERATION RULES

CLEANING AND WASHING OF THE POLYCARBONATE SHEETS.

1. Rinse the sheet with warm water.
2. Wash the sheet with a solution of mild soap or household detergent and warm water, using a soft cloth or sponge to remove dirt.
3. Rinse with cold water and dry with a soft rag to remove water.



Never use abrasives or highly alkaline cleaning compositions for cleaning polycarbonate sheets. Dry rubbing of the surface will damage the protective layer of the cladding and shorten its shelf life. Never rub the surface of polycarbonate sheets with brushes, metallic cloth or other abrasive materials.



when disinfecting the greenhouse from pathogens causing fungal and bacterial diseases, do not use «sulfur blocks» to avoid frame corrosion (blackening).

INSTALLATION INSTRUCTIONS FOR THE «TITAN Arch 196» GREENHOUSE



Be careful during the assembly! Parts have sharp corners. Beware of cuts! The works shall be carried out in gloves.

INTRODUCTION

1. General view of the frame is shown in Fig.1, with tambour - Fig.1a (tambour is to be purchased separately at the customer's request). The frame is assembled from the shaped numbered parts. Middle flanges of the frame are facing the cladding.

2. Indices:

- М** - small;
- б** - big;
- к** - end (of the greenhouse length);
- н** - lower;
- ц** - center;
- д** - door;
- в** - gates;
- п** - right;
- л** - left;
- п** - band;

→ - the arrow indicates the direction of the installation according to the diagrams in the instructions.



Some parts have remaining free holes which is the result of the parts uniformity.



Do not violate instructions! Do not install the bolts and nuts without washers - this may reduce the strength of the frame!

TITAN Arch 196 GREENHOUSE INSTALLATION MANUAL

3. Vocabulary:

Left side - on the left, from the position outside the greenhouse, before the gates.

Right side - on the right, from the position outside the greenhouse, before the gates.

4. Assembling nodes are marked with letters and shown in figures. The greenhouse assembly is carried out using M6 bolts, nuts, washers, self tappers etc. The joints are performed by the part overlay and with fastening on holes. Bolts, nuts and washers shall be put in all the points specified in the instruction.

5. Assembling the greenhouse is presented in stages, at each stage assembling nodes are shown as «before» and «after.» There are no nuts and washers installed from the inner side of the section shown in node figures.

6. During assembly, be careful not to damage the parts, because until they assembled fully, they do not have sufficient rigidity.

Use additional tools for assembly:

- wrench 10;
- screwdriver;
- drill with a $\varnothing 6,5$ bit;
- stepladder height of 3m;
- power jigsaw;
- knife.



INSTALLATION SEQUENCE

Stage	Name	page.
1	End wall assembly	13-17
2	Installation of runners on the end wall	17
3	Power arc assembly	18-20
4	End section assembly: end section without the anteroom assembly; end section with the anteroom assembly; installation of longitudinal stiffness side braces on the end section.	21
5	End section installation	22
6	Extension of the frame length by the insert	23
7	Second side wall section assembly	23
8	Attaching the second end section to the frame	23
9	Doors and gates assembly	24-26
10	Installation of the cladding and sealing	27-35

GENERAL VIEW OF THE GREENHOUSE FRAME WITH EXTENDING INSERTS

Fig. 1

General view of the greenhouse with two inserts, total length is 8,4 m.



GENERAL VIEW OF THE GREENHOUSE FRAME WITH EXTENDING INSERTS




Fig. 1a

ONE «INSERT» extends the greenhouse by 2.13 m. Number of the inserts for the greenhouse is not limited.

GENERAL VIEW OF THE GREENHOUSE FRAME WITH THE ANTEROOM





Fig. 16

General view with the anteroom



INSTALLATION SEQUENCE

STAGE 1

Assembly of the end wall. Assembly is carried out according to the **figure.1.1-1.8**. Assembly of parts is carried out in a horizontal plane by connection on side walls of a shape. Arcs are connected to each other by nesting at length of the cut with alignment of holes (view A).









Fig. 1.1

Fig. 1.2



INSTALLATION SEQUENCE








Fig. 1.3




Determine the places of installation of angles in accordance with **fig.1.8** and install the angles together with the strip **П-11, П-10, П-9, П-5H**



INSTALLATION SEQUENCE

Fig. 1.8
General view of the end wall and location of the angles for fastening of polycarbonate.



STAGE 2

Installation of runners on the end wall.

Assembly is carried out according to the **fig. 2.1**. The assembled end wall is installed in the horizontal. To arcs **4** of the end wall **2k** are alternatively joined end runners **2k 2kH** align the side flanges of shapes. Runners deviate from the vertical under their own weight and abut against side walls of shapes of arcs **4** (until the next operation).




Fig. 2.1

INSTALLATION SEQUENCE

STAGE 3

Assembly of the power arc

Assembly of the power arc is carried out in a horizontal plane similar to the assembly of the end wall (**fig. 3.1-3.5**).




fig. 3.1










fig. 3.2



INSTALLATION SEQUENCE



INSTALLATION SEQUENCE




fig. 3.4
General view of the power arc.



If the greenhouse is equipped with the anteroom, install details of the anteroom on the power arc, intended for the installation of rows with the end headwall.





fig. 3.5
General view of the power arc with the anteroom.

INSTALLATION SEQUENCE

STAGE 4


End section assembly without the anteroom.

Assembly is carried out according to the **fig.4.1**. The assembled power arc (60 kg) is brought to the end wall with the installed runners, is raised to the height of the end runners and joined with their upper ends. It is recommended to connect the outermost and middle runners first.




End section assembly with the anteroom.

Connection the power arc with the anteroom to the end runners **2к** and **2кн (fig.4.2.)**



Installation of longitudinal stiffness side braces.

Installation is carried out in the same way for variants with or without the anteroom.



INSTALLATION SEQUENCE

STAGE 5

End section installation

In the variant of installation of the greenhouse without a foundation, marking of axes is made on the ground in accordance with **fig. 5.1** and holes 70 cm deep are dug for foundation stay braces with supports.

In the variant of installation of the greenhouse **on a foundation** in accordance with **fig. 5.1**, cleat angles are mounted to the foundation for the subsequent fastening on them bottom ends of arcs in accordance with **fig. 5.2** without foundation stay braces.

The end section (weight is about 200 kg) is lifted and placed in a vertical position on a prepared place.

fig. 5.1





fig. 5.2

INSTALLATION SEQUENCE

STAGE 6

Extension of the frame length.

Assembled power arc is brought to the assembled end section at the distance of the main runner and joined to it with the use of main runners **2** and **2H** align the side flanges of shapes **(fig. 6)**.

It is recommended to

connect the outermost and middle runners first, using a stepladder.

Next power arc is joined to the power arc that has already been connected, and so on all the arcs are alternatively joined





fig. 6.1



STAGE 7

The second end section assembly.

Assembly of the second end section is carried out similar to the assembly of the first end section. If the

greenhouse is assembled without inserts **(L-4,2m)**, runners and longitudinal

installed when the end wall is in vertical position similar to **Fig.6.1** stiffness side braces are

STAGE 8

Connecting of the second end section to the frame.

Assembled second end section is brought to the frame at the distance of the main runners and is connected to the frame with the help of them.

It is recommended to connect the outermost and middle runners first, using a stepladder. Lines of runners are leveled and foundation stay braces



are covered 24 with earth. The earth is compacted. If it is necessary, aligning is repeated.

DOORS AND GATES ASSEMBLY

STAGE 9

Doors and gates assembly. Doors and gates assembly is carried out in the same way. Units are shown in figures.

Fig. 9.1



DOORS AND GATES ASSEMBLY




Fig. 9.2
Arrangement of angles for fastening of polycarbonate on the doors.

STAGE 10

Installation of covering



Install covering after fixing the frame on the ground. It is better to cut the sheets using a fret saw or a fine-pitch arm saw.



Install honeycomb polycarbonate with a specified side facing outwards (sunward); this side has a covering layer (make sure to clarify it on buying or prior to installation). Covering layer is usually placed on the side with notations on the shipping film. The film is transparent on the opposite side of a sheet. After marking the sheet but prior to cutting it, mark the side with the covering layer on each piece of the sheet: when the shipping film is removed sheet sides look the same. Shipping film shall be removed from the both sides immediately before fastening covering on the frame.

**PLACE PIECES OF COVERING ON THE END
KEEPING VERTICAL DIRECTION OF HONEYCOMBS.**




Fig. 10.1
Layout of pieces of covering of the end.


CUTTING LIST OF COVERING FOR AN END

CUT POLYCARBONATE SHEET IN STRICT ADHERENCE TO FIG. 10.2
Honeycomb polycarbonate sheet size 2100 x 12000 mm



Fig. 10.2

Cutting list of covering for an end




CUT POLYCARBONATE SHEET IN STRICT ADHERENCE TO FIG. 10.3
Honeycomb polycarbonate sheet size 2100 x 12000 mm



Fig. 10.3

Cutting list of covering for the anteroom. (ref. fig. 16)



FASTENING OF COVERING

Fasten the pieces of covering on the end to the angles with the use of washers and self-tapping screws (**fig.10.4**).




Fig. 10.4

Places of fastening of pieces of covering to each other with the use of a permanent polycarbonate connecting shape are shown in **fig.10.5**.




Fig. 10.5

Using a knife, adjust covering pieces to arcs **4** and girder **20**, and then install sealing profile in accordance with **fig.10.6**




Fig. 10.6

FASTENING OF COVERING

— - places of fastening of door seals.
 ••••• - places of fastening of penofol.




Fig. 10.7

Seals are installed in accordance with **fig. 10.7, 10.8**







Fig. 10.8



Install lugs and handles on the doors and gates.

FASTENING OF COVERING


At first install all joint plates and tingles




FASTENING OF COVERING



FASTENING OF COVERING



FASTENING OF COVERING



Contact information

Austria



Belgium



Croatia



Denmark



Estonia



Finland



France



Germany



Ireland



Italy



Latvia



Lithuania



Nederland



Norway



Poland



Portugal



Spain



Sweden



Switzerland



UK

